

交付金事業

舗装復旧工事（平野六反田他工区）

舗装復旧数量計算書

測点	距離	舗装切断工		舗装版破碎工		表層工 t=5cm						
		断面(m)	数量(m)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	
平面図(1)												
1	No.0 +13.60			3.080	-			3.080	-			
	No.1 +11.43	17.83		3.120	55.27			3.120	55.27			
2	No.1 +11.43			3.100	-			3.100	-			
	No.2 +8.33	16.9		3.440	55.26			3.440	55.26			
3	No.1 +14.00			3.940	-			3.940	-			
	No.1 +18.31	4.31	12.05	3.800	16.68			3.800	16.68			
6	No.2 +8.33			3.440	-			3.440	-			
	No.3 +1.80	13.47		3.180	44.59			3.180	44.59			
7	No.3 +1.80			3.720	-			3.720	-			
	No.3 +3.59	1.79		3.660	6.61			3.660	6.61			
8	No.3 +3.59			3.250	-			3.250	-			
	No.3 +13.15	9.56		3.270	31.17			3.270	31.17			
9	No.3 +13.15			3.270	-			3.270	-			
	No.4 +2.19	9.04		4.340	34.40			4.340	34.40			
10	No.4 +2.19			3.740	-			3.740	-			
	No.4 +4.20	2.01		3.860	7.64			3.860	7.64			
11	No.4 +4.20			4.520	-			4.520	-			
	No.4 +8.00	3.80		4.840	17.78			4.840	17.78			

測点	距離	舗装切断工		舗装版破碎工		表層工 t=5cm					
		断面(m)	数量(m)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	断面(m)	数量(m ²)
12 No.4 +8.00				4.840	-			4.840	-		
No.4 +10.00	2.00			5.790	10.63			5.790	10.63		
14 No.4 +10.39				8.060	-			8.060	-		
No.4 +14.42	4.03			7.880	32.12			7.880	32.12		
図面より			37.66		194.88				194.88		
平面図(2)											
15 No.4 +17.54				3.710	-			3.710	-		
No.6 +12.06	34.52			3.670	127.38			3.670	127.38		
16 No.6 +12.06				3.740	-			3.740	-		
No.6 +13.31	1.25			3.730	4.67			3.730	4.67		
17 No.6 +13.31				3.860	-			3.860	-		
No.7 +6.20	12.89			3.900	50.01			3.900	50.01		
18 No.7 +6.20				3.700	-			3.700	-		
No.7 +11.69	5.49			3.710	20.34			3.710	20.34		
19 No.7 +11.69				3.560	-			3.560	-		
No.7 +12.98	1.29			3.560	4.59			3.560	4.59		
20 No.7 +12.98				3.720	-			3.720	-		
No.8 +2.03	9.05			4.020	35.02			4.020	35.02		
21 No.8 +2.03				3.780	-			3.780	-		
No.8 +7.09	5.06			3.900	19.43			3.900	19.43		

測点	距離	舗装切断工		舗装版破碎工		表層工 t=5cm					
		断面(m)	数量(m)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	断面(m)	数量(m ²)	断面(m)	数量(m ²)
33 No. 14 +7.97				4.120	-			4.120	-		
No. 14 +18.04	10.07			3.500	38.37			3.500	38.37		
34 No. 14 +18.04				3.500	-			3.500	-		
No. 15 +3.96	5.92			3.390	20.39			3.390	20.39		
35 No. 15 +3.96				3.980	-			3.980	-		
No. 15 +11.15	7.19			4.350	29.95			4.350	29.95		
36 No. 15 +11.15				2.990	-			2.990	-		
No. 16 +18.43	27.28			2.990	81.57			2.990	81.57		
37 No. 16 +18.43				2.990	-			2.990	-		
No. 17 +0.57	2.14			5.740	9.34			5.740	9.34		
40 No. 17 +0.57				5.740	-			5.740	-		
No. 17 +5.93	5.36			5.050	28.92			5.050	28.92		
41 No. 17 +5.93				5.050	-			5.050	-		
No. 17 +8.33	2.40			2.770	9.38			2.770	9.38		
42 No. 17 +8.33				2.770	-			2.770	-		
No. 18 +13.00	24.67			2.480	64.76			2.480	64.76		
43 No. 18 +13.00				2.480	-			2.480	-		
No. 18 +19.77	6.77			3.020	18.62			3.020	18.62		
44 No. 18 +19.77				3.020	-			3.020	-		
No. 19 +0.77	1.00			3.230	3.13			3.230	3.13		

土工計算書(2) (DCIP-NS φ 200)

舗装復旧工事(平野六反田他工区) 舗装復旧

土 φ 200-9

番号	種別	土工延長	舗装版切断工		舗装版破砕工		舗装版処分工		機械掘削工		人力掘削		埋戻工(砂)		埋戻工(碎石)		埋戻工(流用土)		発生土処分工		路盤工+影響幅		仮復旧工		土留工					
			単位量 (m/m)	数量 (m)	単位量 ($\frac{m^2}{m}$)	数量 (m^2)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^3}{m}$)	数量 (m^3)	単位量 ($\frac{m^2}{m}$)	数量 (m^2)	単位量 ($\frac{m^2}{m}$)	数量 (m^2)	単位量 (m/m)	数量 (m)	単位量 (m/m)	数量 (m)		
B-1	H=1.90m 市道 As	7.79	2.000	15.58	0.850	6.62	0.043	0.33	1.760	13.71			0.234	1.82	1.488	11.59			1.760	13.71	0.850	4.67	0.850	6.62	0.850	6.62	1.000	7.79		
B-2	H=1.50m 市道 As	8.79	2.000	17.58	0.850	7.47	0.043	0.38	1.420	12.48			0.234	2.06	1.148	10.09			1.420	12.48	0.850	5.27	0.850	7.47	0.850	7.47	1.000	8.79		
B-3	H=1.27m 市道 As	2.20	2.000	4.40	0.750	1.65	0.038	0.08	1.080	2.38			0.202	0.44	0.840	1.85			1.080	2.38	0.750	1.32	0.750	1.65	0.750	1.65				
B-4	H=0.99m 市道 As	15.01	2.000	30.02	0.750	11.26	0.038	0.57	0.870	13.06			0.202	3.03	0.630	9.46			0.870	13.06	0.750	9.01	0.750	11.26	0.750	11.26				
B-5	H=0.90m 市道 As	13.43	2.000	26.86	0.750	10.07	0.038	0.51	0.803	10.78			0.202	2.71	0.563	7.56			0.803	10.78	0.750	8.06	0.750	10.07	0.750	10.07				
B-6	H=0.60m 市道 As	362.40	2.000	724.80	0.750	271.80	0.038	13.77	0.578	209.47			0.202	73.20	0.338	122.49			0.578	209.47	0.750	217.44	0.750	271.80	0.750	271.80				
B-19	H=0.60m 市道 As	6.78	2.000	13.56	0.500	3.39	0.025	0.17	0.305	2.07			0.077	0.52	0.225	1.53			0.305	2.07	0.500	4.07	0.500	3.39	0.500	3.39				
B-23	H=1.27m 市道 As	2.00	2.000	4.00	1.200	2.40	0.060	0.12	1.104	2.21	1.104	2.21	0.826	1.65	1.344	2.69			2.208	4.42	1.200	1.20	1.200	2.40	1.200	2.40	1.000	2.00		
計		418.40 As		836.80 As		314.66 As		15.93		266.16			2.21		85.43			167.26			268.37			舗装本復旧に計上	565.70		314.66		18.58	

土工計算書(2) (DCIP-NS φ 100)

舗装復旧工事(平野六反田他工区) 舗装復旧

土 φ 100-10

番号	種別	土工延長	舗装版切断工		舗装版破碎工		舗装版処分工		機械掘削工		人力掘削		埋戻工(砂)		埋戻工(碎石)		埋戻工(流用土)		発生土処分工		路盤工+影響幅		仮復旧工		土留工					
			単位量 (m/m)	数量 (m)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ² /m)	数量 (m ²)	単位量 (m/m)	数量 (m)	単位量 (m/m)	数量 (m)		
B-7	H=1.38m 市道 As	12.63	2.000	25.26	0.650	8.21	0.033	0.42	0.941	11.88			0.131	1.65	0.800	10.10			0.941	11.88	0.650	8.21	0.650	8.21						
B-8	H=1.21m 市道 As	0.63	2.000	1.26	0.650	0.41	0.033	0.02	0.831	0.52			0.131	0.08	0.689	0.43			0.831	0.52	0.650	0.41	0.650	0.41						
B-9	H=0.60m 市道 As	2.40	2.000	4.80	0.650	1.56	0.033	0.08	0.434	1.04			0.131	0.31	0.293	0.70			0.434	1.04	0.650	1.56	0.650	1.56						
B-24	H=1.21m 市道 As	1.00	2.000	2.00	1.000	1.00	0.050	0.05	0.860	0.86	0.718	0.72	0.507	0.51	1.060	1.06			1.578	1.58	1.000	1.00	1.000	1.00	1.000	1.00	1.000	1.00		
B-27	H=1.21m 市道 As	1.20	2.000	2.40	1.200	1.44	0.060	0.07	1.032	1.24	0.862	1.03	0.611	0.73	1.272	1.53			1.894	2.27	1.200	1.44	1.200	1.44	1.000	1.20	1.000	1.20		
計		17.86	As	35.72	As	12.62	As	0.64		15.54			1.75		3.28			13.82			17.29			23.34			12.62		2.20	

土工計算書(2) (DCIP-NS φ 75)

舗装復旧工事(平野六反田他工区) 舗装復旧

土 φ 75-11

番号	種別	土工延長	舗装版切断工		舗装版破碎工		舗装版処分工		機械掘削工		人力掘削		埋戻工(砂)		埋戻工(碎石)		埋戻工(流用土)		発生土処分工		路盤工+影響幅		仮復旧工		土留工			
			単位量 (m/m)	数量 (m)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ² /m)	数量 (m ²)	単位量 (m/m)	数量 (m)		
B-10	H=1.43m 市道 As	5.06	2.000	10.12	0.600	3.04	0.030	0.15	0.884	4.47			0.109	0.55	0.768	3.89			0.884	4.47	0.600	3.04	0.600	3.04	0.600	3.04	1.000	5.06
B-11	H=1.38m 市道 As	2.15	2.000	4.30	0.600	1.29	0.030	0.06	0.854	1.84			0.109	0.23	0.738	1.59			0.854	1.84	0.600	1.29	0.600	1.29	0.600	1.29		
B-12	H=1.32m 市道 As	5.63	2.000	11.26	0.600	3.38	0.030	0.17	0.818	4.61			0.109	0.61	0.702	3.95			0.818	4.61	0.600	3.38	0.600	3.38	0.600	3.38		
B-13	H=1.00m 市道 As	1.36	2.000	2.72	0.600	0.82	0.030	0.04	0.626	0.85			0.109	0.15	0.510	0.69			0.626	0.85	0.600	0.82	0.600	0.82	0.600	0.82		
B-14	H=0.99m 市道 As	2.60	2.000	5.20	0.600	1.56	0.030	0.08	0.620	1.61			0.109	0.28	0.504	1.31			0.620	1.61	0.600	1.56	0.600	1.56	0.600	1.56		
B-15	H=0.60m 市道 As	11.66	2.000	23.32	0.600	7.00	0.030	0.35	0.386	4.50			0.109	1.27	0.270	3.15			0.386	4.50	0.600	7.00	0.600	7.00	0.600	7.00		
B-16	H=0.42m 市道 As	2.09	2.000	4.18	0.600	1.25	0.030	0.06	0.278	0.58			0.109	0.23	0.162	0.34			0.278	0.58	0.600	1.25	0.600	1.25	0.600	1.25		
B-22	H=0.96m 市道 As	1.30	2.000	2.60	0.500	0.65	0.025	0.03	0.500	0.65			0.089	0.12	0.405	0.53			0.500	0.65	0.600	0.78	0.500	0.65	0.500	0.65		
B-25	H=1.43m 市道 As	1.00	2.000	2.00	0.800	0.80	0.040	0.04	0.864	0.86	0.554	0.55	0.387	0.39	1.024	1.02			1.418	1.42	0.600	0.60	0.800	0.80	0.800	0.80	1.000	1.00
B-26	H=1.00m 市道 As	1.00	2.000	2.00	0.800	0.80	0.040	0.04	0.520	0.52	0.554	0.55	0.387	0.39	0.680	0.68			1.074	1.07	0.600	0.60	0.800	0.80	0.800	0.80		
B-28	H=1.00m 市道 As	3.20	2.000	6.40	1.200	3.84	0.060	0.19	0.780	2.50	0.652	2.09	0.405	1.30	1.020	3.26			1.432	4.58	0.600	1.92	1.200	3.84	1.200	3.84		
B-17	H=1.38m 市道 As	3.10	2.000	6.20	0.500	1.55	0.025	0.08	0.695	2.15			0.077	0.24	0.615	1.91			0.695	2.15	0.600	1.86	0.500	1.55	0.500	1.55		
B-19	H=0.60m 市道 As	2.75	2.000	5.50	0.500	1.38	0.025	0.07	0.305	0.84			0.077	0.21	0.225	0.62			0.305	0.84	0.600	1.65	0.500	1.38	0.500	1.38		
計			42.90	As	85.80	As	27.36	As	1.36	25.98			3.19	5.97	22.94				29.17		舗装本復旧で計上	53.11		27.36		6.06		

番号	種別	土工延長	舗装版切断工		舗装版破碎工		舗装版処分工		機械掘削工		人力掘削		埋戻工(砂)		埋戻工(碎石)		埋戻工(流用土)		発生土処分工		路盤工+影響幅		仮復旧工		土留工			
			単位量 (m/m)	数量 (m)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ² /m)	数量 (m ²)	単位量 (m/m)	数量 (m)		
B-18	H=1.09m 市道 As	2.99	2.000	5.98	0.500	1.50	0.025	0.07	0.550	1.64			0.077	0.23	0.470	1.41			0.550	1.64	0.600	1.79	0.500	1.50	0.500	1.50		
B-19	H=0.60m 市道 As	3.96	2.000	7.92	0.500	1.98	0.025	0.10	0.305	1.21			0.077	0.30	0.225	0.89			0.305	1.21	0.600	2.38	0.500	1.98	0.500	1.98		
B-20	H=0.39m 市道 As	4.54	2.000	9.08	0.500	2.27	0.025	0.11	0.187	0.85			0.066	0.30	0.120	0.54			0.187	0.85	0.600	2.72	0.500	2.27	0.500	2.27		
B-21	H=0.30m 市道 As	2.57	2.000	5.14	0.500	1.29	0.025	0.06	0.142	0.36			0.066	0.17	0.075	0.19			0.142	0.36	0.600	1.54	0.500	1.29	0.500	1.29		
計		14.06	As	28.12	As	7.04	As	0.34		4.06										4.06								
																						舗装本復旧で計上						
														1.00		3.03						15.47			7.04			

舗装復旧工事（平野六反田他工区）

舗装復旧数量計算書

舗装復旧工事（平野六反田他工区）

舗装復旧数量計算書

