

令和3年度  
伊賀市水道施設整備事業 舗装復旧工事(石川工区)

舗装復旧数量計算書  
( $\phi$ 75路線)



## 舗装面積計算書

測点	距離 m	舗装版 切断工	切削オーバーレイ工 (t=5cm)					
			幅員 m	平均幅員 m	面積 m <sup>2</sup>	幅員 m	平均幅員 m	面積 m <sup>2</sup>
№0	0.00	7.10	7.10	-	-			
	+4.50	4.50	6.80	6.95	31.28			
	+4.50	0.00	3.70	-	-			
№1	35.50		3.40	3.55	126.03			
	+6.20	6.20	3.40	3.40	21.08			
	+6.20	0.00	3.10	-	-			
№2	33.80		3.10	3.10	104.78			
№3	40.00		3.10	3.10	124.00			
№4	40.00		2.90	3.00	120.00			
№5	40.00		2.90	2.90	116.00			
№6	40.00		2.90	2.90	116.00			
	+21.90	21.90	2.90	2.90	63.51			
	+24.90	3.00	2.90	2.90	8.70			
№7	15.10		2.90	2.90	43.79			
№8	40.00		2.90	2.90	116.00			
№9	40.00		2.90	2.90	116.00			
	+12.00	12.00	2.90	2.90	34.80			
	+15.00	3.00	2.90	2.90	8.70			
	+20.50	5.50	2.90	2.90	15.95			
合計	380.50	10.00			1166.62			

### 舗装面積計算書

測 点		距離 m	舗装版 切断工	オーバーレイ工 (t=3cm)			切削工 (t=3cm)		
				幅員 m	平均幅員 m	面積 m <sup>2</sup>	幅員 m	平均幅員 m	面積 m <sup>2</sup>
No0		0.00		1.20	-	-			
	+10.00	10.00		3.10	2.15	21.50			
No1		30.00		2.80	2.95	88.50			
	+19.00	19.00		3.90	3.35	63.65			
	+32.00	13.00		4.40	4.15	53.95	1.00	-	-
	+34.10	2.10		4.40	4.40	9.24	1.00	1.00	2.10
合 計		74.10	0.00			236.84			2.10

## 舗装面積計算書

測 点	距離 m	舗装版 切断工	表層工 (t=5cm)			幅員 m	平均幅員 m	面積 m <sup>2</sup>
			幅員 m	平均幅員 m	面積 m <sup>2</sup>			
【市道①】								
№0	0.00	3.00	3.00	-	-			
+6.50	6.50		3.30	3.15	20.48			
+8.50	2.00		5.20	4.25	8.50			
+13.00	4.50		8.40	6.80	30.60			
+18.00	5.00		4.30	6.35	31.75			
+26.00	8.00		3.30	3.80	30.40			
+26.40	0.40		3.30	-	-			
№1	13.60		2.40	2.85	38.76			
№2	40.00		2.30	2.35	94.00			
№3	40.00		2.20	2.25	90.00			
+18.00	18.00		3.30	2.75	49.50			
+19.00	1.00		3.70	3.50	3.50			
+20.00	1.00		5.10	4.40	4.40			
市道①-1 小計	140.00	3.00			401.89			
	(a)	(b)	(c)	(S)	(A)			
Ⓐ +20.00	5.10	5.10	7.20	8.70	13.00			
Ⓑ +24.00	4.50	9.10	7.20	10.40	15.98			
市道①-2 小計	L=4.00m	14.20			28.98			
市道① 合計	144.00	17.20			430.87			

令和3年度  
伊賀市水道施設整備事業 舗装復旧工事(石川工区)

舗装復旧数量計算書  
(給水路線)



## 舗装面積計算書

測 点		距離 m	舗装版 切断工	切削オーバーレイ工 (t=5cm)					
				幅員 m	平均幅員 m	面積 m <sup>2</sup>	幅員 m	平均幅員 m	面積 m <sup>2</sup>
No6	+21.90	0.00		3.40	-	-			
	+24.90	3.00		3.40	3.40	10.20			
No9	+12.00	0.00		4.40	-	-			
	+15.00	3.00		4.40	4.40	13.20			
合 計		6.00				23.40			



## 舗装面積計算書

測 点		距離 m	舗装版 切断工	オーバーレイ工(t=3cm)			切削工(t=3cm)		
				幅員 m	平均幅員 m	面積 m <sup>2</sup>	幅員 m	平均幅員 m	面積 m <sup>2</sup>
No1	+34.10	0.00		4.40	-	-	1.00	-	-
	+36.00	1.90		4.40	4.40	8.36	1.00	1.00	1.90
	+38.00	2.00		6.10	5.25	10.50	1.00	1.00	2.00
No2		2.00		5.70	5.90	11.80	1.00	1.00	2.00
	+11.30	11.30		4.10	4.90	55.37	1.00	1.00	11.30
合 計		17.20	0.00			86.03			17.20

## 舗装面積計算書

測 点		距離 m	舗装版 切断工	表層工 (t=5cm)					
				幅員 m	平均幅員 m	面積 m <sup>2</sup>	幅員 m	平均幅員 m	面積 m <sup>2</sup>
№0		0.00		2.30	-	-			
	+16.00	16.00		2.60	2.45	39.20			
	+35.00	19.00		3.70	3.15	59.85			
	+38.00	3.00		6.50	5.10	15.30			
合 計		38.00	0.00			114.35			

### 舗装面積計算書

測 点	距離 m	舗装版 切断工	表層工 (t=5cm)			幅員 m	平均幅員 m	面積 m <sup>2</sup>
			幅員 m	平均幅員 m	面積 m <sup>2</sup>			
№0	0.00	3.00	3.00	-	-			
№1	40.00		2.70	2.85	114.00			
№2	40.00		2.60	2.65	106.00			
№3	40.00		2.70	2.65	106.00			
	+9.00	9.00	3.50	3.10	27.90			
	+23.00	14.00	2.90	3.20	44.80			
№4	17.00		3.10	3.00	51.00			
	+1.10	1.10	3.10	3.10	3.41			
合 計	161.10	6.10			453.11			

令和3年度  
伊賀市水道施設整備事業 舗装復旧工事(石川工区)

舗装復旧数量計算書  
(消火栓)

