

令和3年度
伊賀市水道施設整備事業
配水管布設工事（青山調整池工区）

本設管数量計算書

労務計算書 (HIVP φ100)

名称	形状・寸法	単位	変更前								変更後									
			計算式								数量	計算式								数量
硬質塩化ビニル管据付工	φ100	m	L =	1.180	仕切弁					=	1.180									
硬質塩化ビニル管切断工	φ100	口	N =	2	切管調書					=	2									
カニカ継手工	φ75	箇所	N =		カチース [°]					=	1									
カニカ継手工	φ100	箇所	N =	VC	カチース [°]					=	2									
RR継手工	φ100	箇所	N =	MFジョイント	エルボ [°]	VC				=	2									
フランジ継手工	φ100	箇所	N =	MFジョイント						=	2									
鋳鉄管撤去工	φ100	m	L =	1.2						=	1.2									
フランジ継手取外工	φ100	箇所	N =	2						=	2									
(削孔工N=1箇所) 削孔	φ150	孔	N =	2						=	2									
モルタル工	1:3	m ³	V =	0.009						=	0.009	(0.075*0.075*π*0.7)-(0.375*0.375*π*0.7)								
型枠工		m ²	A =	0.026						=	0.026	{(0.075*0.075*π)-(0.375*0.375*π)}*2								

番号	種別	土工延長	舗装版切断工		舗装版破碎工		舗装版処分工		機械掘削工		人力掘削		機械埋戻工 (砂)		機械埋戻工 (碎石)		機械埋戻工 (流用土)		発生土処分工		仮復旧工		矢板	
			単位量 (m/m)	数量 (m)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ³ /m)	数量 (m ³)	単位量 (m ² /m)	数量 (m ²)	単位量 (m ² /m)	数量 (m)
土工①	H=0.60m 農道(As)	468.04							0.354	165.69			0.099	46.34	0.248	116.07			0.354	165.69				
土工②	H=0.60m 農道(Co)	8.11							0.326	2.64			0.099	0.80	0.220	1.78			0.326	2.64				
土工③	H=1.60m 農道(As)	6.80							1.397	9.50			0.157	1.07	1.233	8.38			1.397	9.50			H=2.00	6.80
													(Co)											
計									177.83				(Co)	48.21		126.23				177.83				6.80

土工寸法表

番号	種別	管種	管径 (mm)	管外径 (m)	土被り (m)	掘削幅 (m)	管頂人力厚 (m)	掘削深 (m)	機械掘削深 (m)	人力掘削深 (m)	現況舗装厚 (m)	管頂砂厚 (m)	全砂厚 (m)	管控除 (m)	仮復旧厚 (m)	路盤厚 (m)	流用土埋戻 (m)	碎石埋戻 (m)	
土工①	H=0.60m 農道(As)	DCIP-GX	75	0.093	0.600	0.550		0.693	0.643		0.050	0.100	0.193	0.007					0.450
土工②	H=0.60m 農道(Co)	DCIP-GX	75	0.093	0.600	0.550		0.693	0.593		0.100	0.100	0.193	0.007					0.400
土工③	H=1.60m 農道(As)	DCIP-GX	75	0.093	1.600	0.850		1.693	1.643		0.050	0.100	0.193	0.007					1.450

※現況舗装厚を控除

1m当りの土工数量

番号	種別	管種	管径 (mm)	土被り (m)	掘削幅 (m)	舗装切断 (m)	舗装版破砕 (m ²)	舗装版処分 (m ³)	機械掘削 (m ³)	人力掘削 (m ³)	砂埋戻 (m ³)	碎石埋戻 (m ³)	流用土埋戻 (m ³)	発生土処分 (m ³)	路盤工 (m ²)	仮復旧 (m ²)		
土工①	H=0.60m 農道(As)	DCIP-GX	75	0.600	0.550	両側			0.354		0.099	0.248		0.354				
土工②	H=0.60m 農道(Co)	DCIP-GX	75	0.600	0.550	両側			0.326		0.099	0.220		0.326				
土工③	H=1.60m 農道(As)	DCIP-GX	75	1.600	0.850	両側			1.397		0.157	1.233		1.397				
						両側												
						両側												
						両側												
						両側					(Co)							

舗装面積計算書

測点	距離 m	舗装版 切断工	表層工 (t=5cm)			幅員 m	平均幅員 m	面積 m ²
			幅員 m	平均幅員 m	面積 m ²			
No.0	-0.50	0.00	3.60	3.60	-	-		
No.0	+2.50	3.00	3.00	3.60	3.60	10.80		
	+2.50	0.00	2.80	0.80	-	-		
No.5		97.50	97.50	0.80	0.80	78.00		
	+3.10	3.10	3.10	0.80	0.80	2.48		
	+3.10	0.00	2.80	3.60	-	-		
	+6.40	3.30	3.30	3.60	3.60	11.88		
	+6.40	0.00	0.00	3.10	-	-		
	+7.10	0.70	0.70	3.10	3.35	2.35		
	+7.80	0.70	0.70	3.10	3.10	2.17		
	+7.80	0.00	0.00	3.60	-	-		
	+11.10	3.30	3.30	3.60	3.35	11.06		
	+11.10	0.00	2.80	0.80	2.20	0.00		
No.6		8.90	8.90	0.80	0.80	7.12		
No.10		80.00	80.00	0.80	0.80	64.00		
	+2.40	2.40	2.40	0.80	0.80	1.92		
No.13		57.60	115.20	0.80	0.80	46.08		
No.22		180.00	180.00	0.80	0.80	144.00		
	+19.06	19.06	19.06	0.80	0.80	15.25		
IP. 5	-1.37	0.00	0.00	0.55	-	-		
IP. 8	+2.80	13.49	26.98	0.55	0.55	7.42		
合計		473.05	556.14			404.53		

